


~~SECTION~~ AMENDMENT TO BUILDING CODE

Amend Section 2905 (f) to read as follows:

Sec. 2905 (f) Drainage. Provisions shall be made for the control and drainage of surface water around buildings. [See also Section 2907 (d)5.] A drainage system capable of removing excess surface water, subsurface water, and/or excess moisture shall be provided under all pier and beam type foundations over 500 sqft. Such system shall meet the design criteria in the illustration.

Exception: Drainage systems designed and sealed by a professional engineer whose current occupation is in the design and inspection of foundation systems may be submitted for approval.



3" Perforated PVC sloped to drain. Highest point of PVC shall be 1' below void. If grade prohibits gravity flow to street or alley sump pump must be installed on exterior of foundation. Sump pump discharge must be to an approved location. All PVC pipe outside of foundation must be SCH 40.